
HAZARDOUS FUELS REDUCTION DEMONSTRATION



California Society
of American
Foresters
Winter Meeting

Jan 20, 2017

Tad Mason, CEO TSS Consultants



OVERVIEW

- Project Goals
- Summary of Objectives
- Project Sponsors
- Project Implementation
- Results
 - Fire and Fuels
 - Soil Impacts
 - Production and Cost
- Observations
- Recommendations
- Acknowledgements



DISCLAIMERS


- The use of trade, firm, or corporation names in this presentation is for the information and convenience of the audience, and does not constitute an endorsement of any product or service to the exclusion of others that may be suitable
- In accordance with Federal law and U.S. Department of Agriculture policy, this institution is prohibited from discriminating on the basis of race, color, national origin, sex, age, or disability. (Not all prohibited bases apply to all programs.)
- To file a complaint of discrimination, write USDA, Director, Office of Civil Rights, Room 326-W, Whitten Building, 1400 Independence Avenue, SW, Washington, DC 20250-9410 or call (202) 720-5964 (voice and TDD). USDA is an equal opportunity provider and employer.

PROJECT FUNDING AND IMPLEMENTATION

- Funding provided by:
 - National Fire Plan grant USDA Forest Service Pacific Southwest Region and administered by the Watershed Training and Research Center.
 - Southern California Edison
 - California Department of Forestry and Fire Protection
- Implemented by a team lead by:
 - Tad Mason, TSS Consultants
 - Peter Tittmann, UC Berkeley, Center for Forestry
 - Ricky Satomi, UC Berkeley, Center for Forestry
 - David Weise, Fire and Fuels Program USFS PSW Station

PROJECT GOAL

Successfully demonstrate to natural resource managers, landowners, private contractors, agency personnel, concerned public and other stakeholders, the options available to treat excess biomass material.



PROJECT OBJECTIVES - SHORT TERM

Short term objectives of this project include:

- Improved ability of agencies to plan and budget for future fuels treatment projects.
- Development of an informed cadre of local fuels treatment contractors and local stakeholder groups (e.g., fire safe councils, homeowners association, resource conservation districts).
- Outreach to the general public (e.g., media, homeowners, forest landowners) with regards to fuels treatment opportunities, techniques and latest technology.
- Secure public support for increasing the pace and scale of ecologically sound fuels treatment activities.
- Promotion of cost effective, minimum impact fuels treatment alternatives.

PROJECT OBJECTIVES - LONG TERM

Long term objectives of this project include:

- Significant increase in the number of acres treated in support of the reduction of hazardous fuels and improvement of the ecological health of at risk landscapes.
- Reduction of site impacts from fuels treatment activities.
- Creation of long-term sustainable jobs.
- Promotion of an informed public, one that more fully appreciates the complexities of fuels treatment efforts and the statewide challenge of creating and maintaining fire resilient landscapes.
- Improved water yields, timing and quality.

PROJECT LOCATIONS



EQUIPMENT DEPLOYMENT - FALL 2015

| Location | Site Ownership | Vegetation Cover Type | Schedule | |
|-------------------------------------|---|---|----------------|--|
| Shaver lake | Southern California Edison | High elevation Sierra Nevada mixed conifer | October 5-10 | |
| Big Bear Lake | USDA Forest Service, San Bernardino National Forest | High elevation San Bernardino mixed conifer | October 12-17 | |
| Santa Rosa Indian Reservation | Santa Rosa Band of the Cahuilla Indians | Mid elevation chaparral | November 16-21 | |

| TREATMENT SYSTEM | SHAVER LAKE | BIG BEAR LAKE | SANTA ROSA |
|---|------------------|---------------|--------------|
| Air Burner Burn Boss | y (exhibit only) | No Treatment | No Treatment |
| Caterpillar 299D (Skid Steer) | у | у | у |
| FAE Prime Tech PT 175 (Skid Steer) | у | у | y |
| Fecon FTX 128L (Skid Steer) | у | у | у |
| Hand Crew | у | No Treatment | y |
| John Deere JD 210 (Excavator) | у | No Treatment | No Treatment |
| Kaiser S2 (Excavator) | у | No Treatment | Y |
| Star Creek (Goats) | у | No Treatment | No Treatment |
| Takeuchi TB290 (Excavator) | у | у | y |
| Takeuchi TL12 (Skid Steer) | у | у | у |
| Timbco 425D (Excavator) | No Treatment | у | No Treatment |
| Total Acres Targeted for Treatment at Site | 36.97 | 48.5 | 60 |

SKID STEER SYSTEMS









EXCAVATOR SYSTEMS









BIOLOGICAL SYSTEMS








DEMO SCHEDULE

- Day 1: Move in
- Day 2+3+4: Time and motion study.Contractors and media.
- Day 5: Media and general public viewing
- Day 6: Move out



PROJECT LAYOUT



MONITORING - FIELD WORK

Pre-Treatment:


- Browns Line Transect and 1/10 ac circular plots to characterize down woody material and vegetation.
- Photo points.

During Demo:

- Acceleromoter and GPS track location and active work (time and motion monitoring).
- Daily shift reports from operators.
- Video camera (optional).

Post-Treatment:

- Browns Transect and 1/10 ac circular plots to characterize down woody material and vegetation.
- Photo points.




MONITORING PROTOCOL

Soil impacts:

- Characteristics live plant, fine wood, coarse wood, bare soil, rock.
- Disturbance rutting, erosion, compaction, platy. Used USFS Forest Soil Disturbance Protocol. (none (0), low (1), medium (2) or high (3))

Fire Behavior:

- Behave Plus to track rate of spread and flame length.
- Local RAWS weather data at 90th percentile (fuel moistures, wind speed, relative humidity and ambient temperature. Acceleromoter and GPS track location and active work.
- System Productivity and Cost:
 - Shift level data collected. Vendors provided key cost data; equip cost, 0&M, economic life.



FIRE MODELING RESULTS SHAVER LAKE

| TREATMENT SYSTEM | SHRUB COVER (PERCENT) | | 10 HOUR FUEL (TONS/ACRE) | | RATE OF SPREAD (CHAINS/HOUR) | | FLAME LENGTH (FEET) | |
|----------------------------------|--------------------------|------|-----------------------------|------|---------------------------------|------|------------------------|------|
| | Pre | Post | Pre | Post | Pre | Post | Pre | Post |
| Caterpillar 299D | 90 | 62 | 3.54 | 3.54 | 39.9 | 2.3 | 10.5 | 6.3 |
| FAE-Prime Tech PT 175 | 100 | 1 | 4.78 | 3.39 | 20.1 | 0.1 | 10.0 | 0.1 |
| Fecon FTX 128L | 95 | 4 | 2.55 | 6.76 | 23.9 | 0.2 | 7.1 | 0.2 |
| Goats | 70 | 46 | 2.32 | 3.17 | 18.6 | 0.2 | 6.2 | 3.2 |
| John Deere JD210 Hand Crew | 30 | 20 | 2.35 | 3.52 | 16.2 | 5.8 | 7.8 | 2.8 |
| Takeuchi TL12 | 10 | 4 | 3.66 | 3.02 | 26.2 | 0.1 | 6.2 | 0.1 |
| Entire Site | | | | | 23.6 | 0.2 | 8.4 | 1.8 |

FIRE MODELING RESULTS BIG BEAR LAKE

| TREATMENT SYSTEM | SHRUB COVER (PERCENT) | | 10 HOUR FUEL (TONS/ACRE) | | RATE OF SPREAD (CHAINS/HOUR) | | FLAME LENGTH (FEET) | |
|--------------------------|--------------------------|------|-----------------------------|------|---------------------------------|------|------------------------|------|
| | Pre | Post | Pre | Post | Pre | Post | Pre | Post |
| Caterpillar 299D | 80 | 45 | 0.94 | 4.30 | 35.4 | 23.1 | 6.0 | 8.2 |
| Fecon FTX 128L | 65 | 5 | 1.27 | 5.88 | 37.9 | 0.0 | 5.2 | 0.1 |
| FAE-Prime Tech PT 175 | 50 | 5 | 1.05 | 3.84 | 24.0 | 1.8 | 6.9 | 1.5 |
| Takeuchi TB290 | 50 | 10 | 1.91 | 5.45 | 35.4 | 3.8 | 6.7 | 2.5 |
| Takeuchi TL12 | 40 | 5 | 0.58 | 4.76 | 19.5 | 5.0 | 2.9 | 2.9 |
| Timbco 425D | 75 | 5 | 0.12 | 5.88 | 22.1 | 2.6 | 3.1 | 1.8 |
| Entire Site | | | | | 26.3 | 4.1 | 6.2 | 2.9 |

FIRE MODELING RESULTS SANTA ROSA

| TREATMENT SYSTEM | SHRUB COVER (PERCENT) | | 10 HOUR FUEL (TONS/ACRE) | | RATE OF SPREAD (CHAINS/HOUR) | | FLAME LENGTH (FEET) | |
|---------------------------|--------------------------|------|-----------------------------|-------|---------------------------------|------|------------------------|------|
| | Pre | Post | Pre | Post | Pre | Post | Pre | Post |
| Caterpillar 299D | 100 | 32 | 1.44 | 9.10 | 18.8 | 0.1 | 5.5 | 3.3 |
| Fecon FTX 128L | 92 | 0 | 1.14 | 7.95 | 10.2 | 0.5 | 2.6 | 0.4 |
| Hand Crew | 93 | 40 | 4.59 | 6.42 | 44.2 | 0.2 | 14.8 | 3.8 |
| Kaiser S2 Spider | 95 | 20 | 5.07 | 9.99 | 55.4 | 0.2 | 16.9 | 0.2 |
| FAE - Prime Tech PT175 | 95 | 20 | 5.40 | 6.99 | 60.1 | 0.1 | 16.6 | 0.1 |
| Takeuchi TB290 | 100 | 0 | 3.64 | 7.92 | 46.5 | 0.4 | 14.0 | 0.3 |
| Takeuchi TL12 | 95 | 15 | 7.16 | 13.69 | 61.4 | 0.1 | 18.0 | 0.1 |
| Entire Site | | | | | 27.3 | 0.2 | 12.4 | 0.9 |

SOIL IMPACT ANALYSIS RESULTS SHAVER LAKE

| TREATMENT SYSTEM | WOODY COVER (PERCENT) | | LIVE VEG COVER (PERCENT) | | | BARE SOIL CENT) | POST TREATMENT DISTURBANCE RATING |
|------------------------|--------------------------|-------|-----------------------------|-------|-------|--------------------|-----------------------------------|
| | Pre | Post | Pre | Post | Pre | Post | |
| Caterpillar 299D | 70.00 | 73.33 | 86.67 | 46.67 | 0.00 | 6.67 | 0.26 |
| FAE Prime TechPT175 | 46.67 | 86.67 | 86.67 | 13.33 | 6.67 | 26.67 | 0.06 |
| Fecon FTX 128L | 51.67 | 50.00 | 76.67 | 20.00 | 23.34 | 10.00 | 0.04 |
| Hand Crew | 60.00 | 70.00 | 60.00 | 40.00 | 33.33 | 0.00 | 0.00 |
| Goats | 70.00 | 63.33 | 93.33 | 66.67 | 6.67 | 20.00 | 0.00 |
| John Deere JD 210G | 60.00 | 70.00 | 60.00 | 40.00 | 33.33 | 0.00 | 0.00 |
| Takeuchi TB290 | 70.00 | 53.33 | 60.00 | 6.67 | 26.67 | 33.33 | 0.00 |

SOIL IMPACT ANALYSIS RESULTS BIG BEAR LAKE

| TREATMENT SYSTEM | WOODY COVER (PERCENT) | | LIVE VEG COVER (PERCENT) | | | BARE SOIL CENT) | POST TREATMENT DISTURBANCE RATING |
|---------------------------|--------------------------|-------|-----------------------------|-------|-------|--------------------|-----------------------------------|
| | Pre | Post | Pre | Post | Pre | Post | |
| Caterpillar 299D | 30.00 | 33.33 | 60.00 | 26.67 | 26.67 | 33.33 | 0.27 |
| FAE - Prime Tech PT175 | 100.00 | 60.00 | 46.67 | 53.33 | 20.00 | 20.00 | 0.40 |
| Fecon FTX 128L | 36.67 | 53.33 | 53.33 | 0.00 | 13.33 | 46.67 | 0.80 |
| Takeuchi TB290 | 76.67 | 50.00 | 13.33 | 33.33 | 6.67 | 13.33 | 0.13 |
| Takeuchi TL 12 | 46.67 | 60.00 | 46.67 | 53.33 | 33.33 | 20.00 | 0.33 |
| Timbco 425D | 66.67 | 50.00 | 80.00 | 13.33 | 20.00 | 60.00 | 0.27 |

SOIL IMPACT ANALYSIS RESULTS SANTA ROSA

| TREATMENT SYSTEM | WOODY COVER (PERCENT) | | LIVE VEG COVER (PERCENT) | | | BARE SOIL CENT) | POST TREATMENT DISTURBANCE RATING |
|---------------------------|--------------------------|-------|-----------------------------|-------|-------|--------------------|-----------------------------------|
| | Pre | Post | Pre | Post | Pre | Post | |
| Caterpillar 299D | 50.00 | 50.00 | 60.00 | 20.00 | 6.67 | 6.67 | 1.60 |
| FAE - Prime Tech PT175 | 40.00 | 50.00 | 73.33 | 0.00 | 46.67 | 6.67 | 1.80 |
| Fecon FTX 128L | 53.33 | 53.33 | 80.00 | 0.00 | 40.00 | 13.33 | 0.4 |
| Hand Crew | 46.67 | 50.00 | 66.67 | 6.67 | 46.67 | 13.33 | 1.2 |
| Kaiser S2 Spider | 53.33 | 53.33 | 80.00 | 13.33 | 53.33 | 6.67 | 0.80 |
| Takeuchi TB290 | 53.33 | 53.33 | 80.00 | 6.67 | 20.00 | 0.00 | 1.13 |
| Takeuchi TL 12 | 50.00 | 50.00 | 66.67 | 0.00 | 60.00 | 0.00 | 1.47 |

RESULTS - MASTICATION PRODUCTIVITY AND COST

| | | Shave | r Lake | Big Bea | r Lake | Santa | Rosa |
|--------------------|--------------------------|----------------------------|------------------------|----------------------------|------------------------|----------------------------|------------------------|
| Treatment Type | Treatment System | Production (hour/ acre) | Cost Rate (\$/acre) | Production (hour/ acre) | Cost Rate (\$/acre) | Production (hour/ acre) | Cost Rate (\$/acre) |
| Hand Crew | CCC Hand Crew | 7.5 | \$1,681.63 | - | - | - | - |
| Hand Crew | Ramona Tribe | - | - | - | - | 14.0 | \$2,713.78 |
| Goat Herd | Star Creek Land Stewards | 8.1 | \$330.74 | - | - | - | - |
| Boom Mount | John Deere JD 210G | 9.9 | \$614.50 | - | - | - | - |
| Boom Mount | Kaiser S2 Spider | 3.7 | \$426.46 | - | - | 3.5 | \$398.97 |
| Boom Mount | Takeuchi TB290 | 8.2 | \$348.37 | 5.5 | \$233.64 | 9.1 | \$385.43 |
| Boom Mount | Timbco 425 D | - | - | 1.6 | \$166.56 | - | - |
| Integrated Machine | FAE - Prime Tech PT175 | 2.2 | \$166.21 | 2.6 | \$192.34 | 1.4 | \$107.41 |
| Integrated Machine | Fecon FTX 128L | 2.7 | \$203.48 | 3.4 | \$253.88 | 1.0 | \$73.54 |
| Skid Steer Mount | Caterpillar 299D | 2.0 | \$122.81 | 4.5 | \$274.16 | 1.3 | \$76.86 |
| Skid Steer Mount | Takeuchi TL 12 | 2.6 | \$112.12 | 3.9 | \$168.70 | 1.8 | \$77.13 |



OBSERVATIONS - FIRE AND FUELS

Treatment Systems

All treatment systems systems significantly altered fuel profiles at all three sites.

Increased Down Woody Material

Amount of down woody material increased as a result of treatment – especially in the 10 to 100 hour fuel classes. Predicted fire behavior (spread, flame length, heat) were reduced, often to levels that would allow direct attack by hand crews.

Potential Fire Damage to Root Systems/Topsoil

Elevated levels of down woody material (post treatment), may contribute to below ground root damage in the event of a fire. However, as woody material decomposed over time and is incorporated into the soil, this potential damage will be mitigated.

25



OBSERVATIONS - SOIL IMPACTS

Overall Soil Impacts

Overall soil impacts were minimal across all three sites. Hand crews and goats had almost no impact (not surprising).

Treatment Prescriptions

Different terrain, ecosystem types and management objectives result in very site specific treatment prescriptions. Prescriptions will impact treatments, which in turn have potential to more significantly impact soils.

OBSERVATIONS - PRODUCTION RATES AND COSTS

Productivity and Cost

Production rates and costs differ based on treatment system, site and complexity of treatment prescription.

Vegetation Consistency, Terrain and Prescription

Cost per acre rate was lowest for nearly all equipment at the Santa Rosa site. This was primarily due to very consistent veg (shrub dominated site), gentle terrain and a very simple prescription. Big Bear site had the most expensive cost, primarily due to varied veg types and complex treatment prescription.

Goats and Hand Crews

Goats and hand crews were by far the mostly costly systems. Suggest deployment on sensitive sites.



OBSERVATIONS - DEMO ATTENDANCE

Participation

Almost 300 guests attended the demos. Guest demographics was wide ranging – from students (high school and University), to land managers, tribal representatives, media (print and TV), fire agencies.

Registration

Use of on-line registration worked well and facilitated followup and delivery of results. Overall soil impacts were minimal across all three sites. Hand crews and goats had almost no impact (not surprising).

Media Participation

Attracting media participation can be very challenging. Only four media reps attended (all at the Shaver Lake demo).

Outreach

Strongly suggest use of communications/outreach plans for each demo as target audiences will shift depending on demo location.



RECOMMENDATIONS FOR FUTURE DEMONSTRATIONS

Extend Post-Treatment Monitoring

Consider monitoring post-treatment conditions over an extended period of time (5 to 10 years). Key variables to monitor include soil conditions, veg response, and woody debris decomposition rates.

Steep Terrain Demos

Replicate HFRD on steep terrain. Much of the terrain considered at risk to wildfire in CA is located on steep ground (> 35% slope).

Woody Material Collection and Processing

Value-added uses for excess forest biomass material are expanding (thermal, power, soil amendments, advance biofuels) as innovative conversion technologies evolve. Conduct equipment trials to test techniques to optimize collection, processing and transport of forest biomass material.

ACKNOWLEDGMENTS - PART I

Steering Committee

- Larry Swan, USFS, State and Private Forestry, Region 5
- Bruce Hartsough, UC Davis, Biological and Agricultural Engineering Department
- Steven Brink, California Forestry Association
- Angie Lottes, California Statewide Wood Energy Team
- Ed Smith, The Nature Conservancy
- Glen Barley, CAL FIRE
- Marva Willey, USFS, Fuels Program Region 5
- Ted Luckham, Southern California Edison

Implementation Team

- Peter Tittmann, UC Center for Forestry
- Ricky Satomi, UC Center for Forestry

ACKNOWLEDGMENTS - PART II

Field Sampling and Analysis Team

- Gloria Burke, USFS Pacific Southwest Station
- Joey Chong, USFS Pacific Southwest Station
- David Weise, Fire and Fuels Program, USFS Pacific Southwest Station
- Raymond Aguayo, USFS Mountain Top Ranger District, San Bernardino National Forest

Science Advisory Committee

- David Weise, Fire and Fuels Program, USFS Pacific Southwest Station
- Peter Tittmann, UC Center for Forestry
- Ricky Satomi, UC Center for Forestry
- Max Moritz, UC Cooperative Extension

MORE INFORMATION

Copies of the HFRD final report are available for download from the UCANR Woody Biomass Utilization website:

http://ucanr.edu/sites/WoodyBiomass/Technical_Assistance/ Hazardous_Fuels_Reduction_Demonstration_753/

In addition the site hosts before/after images, equipment video clips, and equipment images.



QUESTIONS or HECKLING REMARKS?



Tad Mason, Forester TSS Consultants 916.600.4174

tmason@tssconsultants.com

www.tssconsultants.com